

Upto 1 of

**14th. CORRIGENDA & ADDENDA  
FOR SCHEDULE OF RATES P.W.D.(WB) w.e.f.01.11.2017  
Volume -I (for building, material & labour)**

**SECTION -I Building works.**


**(a) CORRIGENDA**


D.O.P.: :08.03.2021


Please read in place of sl no. 1, Item no. - New(i) of chapter C (Brick works, Concrete works etc.) of 13th. Corrigenda & addenda dated 26.02.2021 regarding chemical for rebar anchoring.....


N.B. - Both description of item & rates for supplying and application of chemical for post installed rebar ..... will be as per 15th. corrigenda & addenda

Sl No.	Chapter No. & Item No.	Description of Item	Unit	Rate (Rs.)													REMARKS
				Kolkata / 24 Pgs (N & S) /Area of Kalyani Sub	Bardhaman	Purulia	Birbhum	Howrah/ Hoogly	Medinipur (E)	Medinipur (W)	Bankura	Nadia excluding area of Kalyani Sub Div	Murshidabad	Meida	Darjeeling except plains of Sitiguri Sub Divn.	Jalpaiguri, Alipurdwar, plains of Sitiguri Sub Divn. & Area of Haldibari PS	
1	Item No - New (i) of Chapter-C (Brick works, Concrete works etc.)	<p>Supplying and application of chemical for post installed rebar connection by using ETA approved for seismic criteria in rebar connection , including drilling hole to the required depth by rotary hammer drill, cleaning with brush &amp; jet of clean air, filling chemical using serrated nozzle to eliminate mixing error and in a voidless manner including charges for all tools &amp; plants. Application to be designed for post - installed rebars as per EC2/TR023 or relevant tested and accepted design guidelines and the design document to be furnished by the manufacturer. The chemical should have ETA approval for seismic criteria of rebar fixing which should be furnished by manufacturer. The installation and the setting instructions should be strictly followed as per manufacturer's specifications as approved by EIC prior to drilling along with post - installed rebar embedment design report. The existing concrete member should be scanned using rebar scanner to avoid hitting existing reinforcement in concrete during drilling.</p> <p>Notes :-</p> <p>1) This rate is excluding the cost of scaffolding.</p> <p>2) This work should not be executed without specific permission of Superintending Engineer of the respective circle and injection process should be executed in the presence of officer not below the rank of Assistant Engineer to supervise the work minutely.</p> <p>3) Rebar grouting is specifically required for extension and strengthening purpose of old or existing RCC structural members with new RCC structural members through rebar fixing chemical item without breaking beam, coloumn, roof slab, lintel, ceiling etc.</p>															
		i) Cost of post installed rebaring application with chemical as specified for 8 mm dia per cm of depth	Cm	16	16	16	16	16	16	16	16	16	16	16	16	16	16
		ii) Cost of post installed rebaring application with chemical as specified for 10 mm dia per cm of depth	Cm	18	18	18	18	18	18	18	18	18	18	18	18	18	18
		iii) Cost of post installed rebaring application with chemical as specified for 12 mm dia per cm of depth	Cm	21	21	21	21	21	21	21	21	21	21	21	21	21	21
		iv) Cost of post installed rebaring application with chemical as specified for 16 mm dia per cm of depth	Cm	27	27	27	27	27	27	27	27	27	27	27	27	27	27
		v) Cost of post installed rebaring application with chemical as specified for 20 mm dia per cm of depth	Cm	42	42	42	42	42	42	42	42	42	42	42	42	42	42
		vi) Cost of post installed rebaring application with chemical as specified for 25 mm dia per cm of depth	Cm	63	63	63	63	63	63	63	63	63	63	63	63	63	63

  
**DIPAK GHOSH**  
 Superintending Engineer  
 Bridge Planning Circle  
 Member of Combined  
 Schedule Committee PW Dte. &  
 PW(Roads) Dte.

  
**GAUTAM ADAK**  
 Superintending Engineer  
 Survey & Design Circle  
 Member of Combined  
 Schedule Committee PW Dte. &  
 PW(Roads) Dte.

  
**RAJIB CHATTARAJ**  
 Superintending Engineer  
 Planning & Monitoring Circle  
 Convener of Combined  
 Schedule Committee PW Dte. &  
 PW(Roads) Dte.

  
**AMITABHA SENGUPTA**  
 E-in- C & Ex-Officio Secretary  
 Public Works Department,  
 Chairman of Combined  
 Schedule Committee PW Dte. & PW(Roads) Dte.