

**2nd. ADDENDA & CORRIGENDA  
TO THE PWD (WB), SCHEDULE OF RATES- 2018  
Volume III: Road & Bridge Works**

**Dated : 10<sup>th</sup> January 2019.**

**A. CORRIGENDA OF SCHEDULE OF RATES - 2018**

**1. Following Corrections are to be made to the Table3.3-1 of Section 3.3**

Section	Item No. / Page No	Description	Unit	In Place of	To be read as
Section-3.3  Approximate requirement of materials for different works	5.21  Page - 216	20 mm thick Mix Seal Surfacing (MSS) :	Sqm.		
		a) Type - A			
		Stone chips 5.6mm		0.020 cum	0.0081 cum
		Stone chips 2.8mm		*****	0.0119 cum
		Stone dust		0.007 cum	0.007 cum
		Bitumen		2.20 kg	2.20 kg
		b) Type - B			
		Stone chips 11.2mm		0.0067 cum	0.0016 cum
		Stone chips 5.6mm		0.0162 cum	0.0142 cum
		Stone chips 2.8mm		****	0.0072 cum
Stone dust	0.0041 cum	0.004 cum			
Bitumen	1.90 kg	1.90 kg			

**2. Following Corrections are to be made to the TABLE NO. I-2 EX-OUTLET PRICES OF BITUMEN (Page 219 of SOR 2018):**

Page No.	Sl. No. / Item	Description of item	Unit	In place of		To be read as	
				Rates at outlets (₹)		Rates at outlets (₹)	
1	2	3	4	5		6	
				At Haldia	At Dhulagarh Jn.(on NH-6)	At Haldia	At Dhulagarh Jn.(on NH-6)
219	<b>TABLE I-2</b>	<b>EX-OUTLET PRICES OF BITUMEN :</b>					
	1.	Bitumen (Bulk) :VG-10	MT	36020.00	***	29490.00	***
	2.	Bitumen (Packed) :VG-10	MT	39320.00	***	32790.00	***
	3.	Bitumen (Bulk) :VG-30	MT	36820.00	***	30290.00	***
	4.	Bitumen (Packed) :VG-30	MT	40120.00	***	33590.00	***
	5.	Bitumen (Bulk) :VG-40	MT	38660.00	***	31140.00	***
	6.	Bitumen (Packed) :VG-40	MT	***	***	***	***
	7.	Penetration gr. Bitumen 10/20 (Packed)	MT	***	41780.00	***	34750.00
	8.	Bituminous Emulsion (Bulk) MS Type	MT	29840.00	***	24910.00	***
	9.	Bituminous Emulsion (Packed) MS Type	MT	***	34746.00	***	31950.00
	10.	CRMB - 55 (Bulk)	MT	37760.00	***	31890.00	***
	11.	CRMB - 55 (Packed)	MT	41300.00	***	35430.00	***
	12.	CRMB - 60 (Bulk)	MT	37900.00	***	32150.00	***
	13.	CRMB - 60 (Packed)	MT	41440.00	***	35690.00	***
	14.	Polymer modified emulsion (Packed)	MT	***	44746.00	***	34000.00
15.	Polymer modified Bitumen (PMB-40) (Bulk)	MT	***	48320.00	***	35500.00	

## 3. Following corrections are to be made to the item as shown below:

Page No.	Item / Sl. No.	In place of	To be read as
235	2.14	<b>Dismantling of Flexible Pavements</b> Dismantling of flexible pavements and disposal of dismantled materials upto a lead of 100 m, stacking serviceable and unserviceable materials separately as per Technical Specifications Clause 202 for Rural Roads of MORD.	<b>Dismantling of Flexible Pavements</b> Dismantling of flexible pavements and disposal of dismantled materials upto a lead of <b>1000 m</b> , stacking serviceable and unserviceable materials separately as per Technical Specifications Clause 202 for Rural Roads of MORD.
262	5.20	<b>Recycling of Bituminous Pavement with Central Recycling Plant</b> Recycling pavement by cold milling of existing bituminous layers, planning the surface after cold milling, reclaiming excavated material to the extent of 30 per cent of the required quantity, hauling and stockpiling the reclaimed material near the central recycling plant after carrying out necessary checks and evaluation, adding fresh material including rejuvenators as required, mixing in a hot mix plant, transporting and laying at site and compacting to the required grade, level and thickness, all as specified in Clause 519.	<b>Recycling of Bituminous Pavement with Central Recycling Plant</b> Recycling pavement by cold milling of existing bituminous layers, planning the surface after cold milling, reclaiming excavated material to the extent of 30 per cent of the required quantity, hauling and stockpiling the reclaimed material near the central recycling plant after carrying out necessary checks and evaluation, adding fresh material including rejuvenators as required, mixing in a hot mix plant, transporting and laying at site and compacting to the required grade, level and thickness, all as specified in Clause 519.  <b>Note: Add cost &amp; Carriage of materials as per requirement vide Table 3.3-1 of section-3 under item no. 5.20.</b>
295	12.13	<b>Providing Steel liner</b> for Curbs and 6 mm thick for Steining of Wells including fabricating and setting out as per detailed drawing.	<b>Providing Steel liner for 10 mm thick</b> Curbs and 6 mm thick for Steining of Wells including fabricating and setting out as per detailed drawing.
299	12.20 (Note-1)	Construction wing is to add cost of cement, <b>sand</b> and cost & carriage of coarse aggregates as per requirement vide Table 3.2-1 of Section only to arrive at consolidated rate.	Construction wing is to add cost of cement and cost & carriage of coarse aggregates as per requirement vide Table 3.2-1 of Section 3.2, only to arrive at consolidated rate.
331	18.02(c) (Description of Item)	By mechanical means (without milling machine)	<b>By mechanical means (with milling machine)</b>



(TAPASH KR. DEY)  
Superintending Engineer  
Bridge Planning Circle  
Member of the Combined  
Schedule Committee  
PW Dte. & PW (Roads) Dte.



(GAUTAM ADAK)  
Superintending Engineer  
Survey & Design Circle  
Member of the Combined  
Schedule Committee  
PW Dte. & PW (Roads) Dte.



(Sankar Dutta)  
Superintending Engineer  
Planning & Monitoring Circle  
Member Convener of the  
Combined Schedule Committee  
PW Dte. & PW (Roads) Dte.



(TAPAS MUKHOPADHYAY)  
Engineer-in-Chief  
Public Works Department  
Chairman of the Combined  
Schedule Committee  
PW Dte. & PW (Roads) Dte.