

**3rd. Corrigenda & Addenda
FOR SCHEDULE OF RATES PWD(W.B) wef 21.07.2019
Volume-II(For Sanitary & Plumbing Works)**

**SECTION (B) - SANITARY AND DRAINAGE WORKS
(B)-(II) SOIL PIPE AND FITTINGS**

*B.B./IT
A. Public. Sec.
for 29/7/19*

Item No.	Description of Item	All Districts of West Bengal		
		Unit	(Rs)	(Rs.)
	Supply of Unplasticized Non-Pressure Polyvinyl Chloride (PVC-U) Pipes (SN 8, DSR 34) & fittings for use in Underground drainage and sewerage systems conforming to IS-15328-2003		Solvent Cement Type	Rubber Ring Type
NEW	(A) (i) Single Socketed 3 Meter Length (SN2)			
	(a) 160mm	metre.	995	1003
	(b) 200mm	metre.	1525	1532
	(A) (ii) Single Socketed 3 Meter Length (SN4)			
	(a) 125mm	metre.	651	657
	(b) 160mm	metre.	1045	1051
	(A) (iii) Single Socketed 3 Meter Length (SN8)			
	(a) 75mm.	metre.	287.3	342.55
	(b) 110mm	metre.	570	576
	(c) 160mm	metre.	1221	1227
	(d) 200mm	metre.	1918	1920
	(B) Fittings			
	(i) Coupler			
	(a) 110mm	Per Pc.		186
	(b) 160mm	Per Pc.		348
	(c) 200mm	Per Pc.		740
	(ii) Plain Tee			
	(a) 110mm	Per Pc.		263
	(b) 160mm	Per Pc.		526
	(ix) Bend 45°			
	(a) 110mm	Per Pc.		227
	(b) 160mm	Per Pc.		442
	(x) Reducer			
	(i) 160mm X 110mm	Per Pc.		225


For 29/7/19
SE, BPC


for 29/7/19
SE, SDC


for 29/7/19
SE, P&MC


for 29/7/19
Engr. G. P. W. D. &
Ex-Officio Secretary
Public Works Department
Government of West Bengal
Nabanna, Howrah-711102

Item No.	Description of Item	All Districts of West Bengal		
		Unit	(Rs)	(Rs.)
2NEW	Labour for fitting and fixing Unplasticized non-pressure Poly Chloride (P.V.C-U) pipes for underground drainage and sewerage system (IS 15328:2003) including cost of jointing materials etc. fitting and fixing all necessary specials, cutting pipes, cutting holes in walls or R.C. floor where necessary and mending good all damages excluding the cost of masonry or concrete work, if necessary, but including the cost and fitting and fixing holder bat clamps (any floor) or for underground work including cutting trenches upto 1.5 metre and refilling the same complete as per direction of the Engineer-in-charge. (Payment will be made on centre line measurement of the total pipeline including specials.			
	(i) 75mm	metre.		73
	(ii) 110mm	metre.		84
	(iii) 125mm	metre.		91
	(iv) 160 mm	metre.		93
	(v) 200mm	metre.		102


TAPASH KR. DEY
 Superintending Engineer
 Bridge Planning Circle
 Member of Combined
 Schedule Committee PW Dte. &
 PW(Roads) Dte.


GOUTAM ADAK
 Superintending Engineer
 Survey & Design Circle
 Member of Combined
 Schedule Committee PW Dte. &
 PW(Roads) Dte.


SANKAR DUTTA
 Superintending Engineer
 Planning & Monitoring
 Circle
 Convener of Combined
 Schedule Committee PW Dte. &
 PW(Roads) Dte.


TAPAS MUKHOPADYAY
 Engineer-in- Chief
 Public Works Department
 Member of Combined
 Schedule Committee PW Dte. &
 PW(Roads) Dte.