

5th CORRIGENDA & ADDENDA
FOR SCHEDULE OF RATES OF PWD (W.B) wef 01.12.2015
Volume-I: (For Building Works, Materials & Labour)

(A) CORRIGENDA

Date: 04.11.2016

Page No.	Chapter & Item no. and reference	In place of	Please read	Remarks
250	Item No:3 of Chapter-U of PWD SOR Vol-I wef 01.12.2015	100 mm th. Autoclave aerated concrete block work with size 625 mm x 250 mm x 125mm -Grade-I quality, having drying Shrinkage less than 0.05% conforming to IS: 2185 (Part-3)-1984 made up of fly ash (conforming to IS: 3812-1981, with permissible loss on ignition upto 6%), lime, cement and laid in cement mortar(1:6) complete in all respect as per direction & satisfaction of Engineer-in-Charge .	100 mm th. Autoclave aerated concrete block work with size 625 mm x 250 mm x 100mm - Grade-I quality, having drying Shrinkage less than 0.05% conforming to IS: 2185 (Part-3)-1984 made up of fly ash (conforming to IS: 3812-1981, with permissible loss on ignition upto 6%), lime, cement and laid in cement mortar(1:6) complete in all respect as per direction & satisfaction of Engineer-in-Charge .	Except Description of the Item, all other columns remain unchanged.
57	Item No:31B of Chapter-D of PWD SOR Vol-I wef 01.12.2015	Supplying, fitting & fixing granite slabs 15mm to 18 mm. thick with uniform texture & without decorative veins in columns, wall, facia etc. with 15 mm thick [avg] cement mortar (1:2) including making suitable arrangements to hold the stones properly by brass / copper hooks including pointing in cement mortar (1:2) (1 white cement : 2 marble dust) with admixture of pigment matching the stone shades all complete as per direction of the Engineer-in-charge including cost of all materials, labours, scaffolding, staging ,curing and roughening of concrete surface complete. [Using cement slurry at back side of granite @ 4.4 kg/sq.m & white cement slurry for joint filling @ 1.8 kg/sq.m]	Supplying, fitting & fixing granite slabs 15mm to 18 mm. thick with uniform texture & without decorative veins in columns, wall, facia etc. with 15 mm thick [avg] cement mortar (1:2) including making suitable arrangements to hold the stones properly by brass / copper hooks including pointing in cement mortar (1:2) (1 white cement : 2 marble dust) with admixture of pigment matching the stone shades all complete as per direction of the Engineer-in-charge including cost of all materials, labours, scaffolding, staging ,curing and roughening of concrete surface complete. - Area of each Granite slab >0.6 upto 1.0 Square meter. [Using cement slurry at back side of granite @ 4.4 kg/sq.m & white cement slurry for joint filling @ 1.8 kg/sq.m]	Except Description of the Item, all other columns remain unchanged.
A-2	GENERAL CONDITION Sl.9	Rates of all items are inclusive of labour & material charges with all other relevant cost towards Sales Tax, Royalty, Octroi, Toll Tax, Ferry Charges, VAT etc. as may have to be incurred by the contractor for the respective items of works to be executed to proper and complete finish.	Rates of all items are inclusive of labour & material charges with all other relevant cost towards Sales Tax, Royalty, Octroi, Toll Tax, Ferry Charges, VAT etc. (exclusive of Service Tax) for the respective items of works to be executed to proper and complete finish.	
B-5	GENERAL SPECIFICATION Sl. A-7	Cement : No cement except those supplied by the department or approved by Engineer-in-Charge shall be used in work or brought to site by contractor. Cement bags must be stored in a water-tight shed having wooden floor or platforms raised at least 50 mm. from ground as approved by the Engineer-in-Charge. Cement which is partially set or which is lumpy or caked is to be treated as damaged and shall be removed from the site immediately.	Cement : No cement except those supplied by the department or approved by Engineer-in-Charge shall be used in work or brought to site by contractor. Cement bags must be stored in a water-tight shed having wooden floor or platforms raised at least 50 mm. from ground as approved by the Engineer-in-Charge. Cement which is partially set or which is lumpy or caked is to be treated as damaged and shall be removed from the site immediately. For list of relevant IS Code for Cement to be used in work Page-B-65 of Volume-I & Clause 2.1.4 (Page-9) of Volume-III of Combined PWD Schedule Mandatory tests before use of Cement material into works are given in clause 3.0 (Page-188,189 & 190) Volume-III of Combined PWD Schedule, may be seen.	
B-5	GENERAL SPECIFICATION Sl. A-8	Steel: All steel shall be clean and free from loose mill scales, dust, loose rust and coats of paints, oil or other coatings. Any scale or loose rust shall be removed before use, even though the same may have been supplied by the Department without any claim for extra charge for the same. No steel excepting those supplied by the Department or approved by the Engineer-in-Charge shall be used in work or brought to site by the contractor.	Steel: All steel shall be clean and free from loose mill scales, dust, loose rust and coats of paints, oil or other coatings. Any scale or loose rust shall be removed before use, even though the same may have been supplied by the Department without any claim for extra charge for the same. No steel excepting those supplied by the Department or approved by the Engineer-in-Charge shall be used in work or brought to site by the contractor. For list of relevant IS Code for reinforcement in concrete page-B-66 of Volume-I & for structural steel clause 2.1.7.5 (Page-12) of Volume-III may be seen. Mandatory tests before use of steel materials into works are given in clause 2.0 Steel/ Iron (Page-185,186 & 187) Volume-III of Combined PWD Schedule, may be seen.	

**5TH CORRIGENDA & ADDENDA
FOR SCHEDULE OF RATES OF PWD (W.B) wef 01.12.2015
Volume-I: (For Building Works, Materials & Labour)**

(c) CORRIGENDA

Date: 04.11.2016

Sl No.	Ref. Page No.	Chapter No. & Item No.	Description of Item	Unit	Rate (Rs.)														REMARKS				
					Kolkata / 24 Pgs (N & S) /Area of Kalyani Sub Div	Bardhaman	Purulia	Birbhum	Howrah/ Hoogly	Medinipur (E)	Medinipur (W)	Bankura	Nadia excluding area of Kalyani Sub Div	Murshidabad	Malda	Darjeeling except plains of Siliguri Sub Divn.	Jaipur, Jharkhand, plains of Siliguri Sub Divn. & Area of Haldibari PS	Coochbehar excluding the area of Haldibari PS		Uttar/ Dakshin Dinajpur Dist.			
1	28	Item No - 15 a (i) of Chapter-C	Reinforcement for reinforced concrete work in all sorts..... complete as per drawing and direction. (a) For works in foundation, basement and upto roof of ground floor/upto 4 m																				
				In Place of																			
				(i) Tor steel/Mild Steel	M.T.	56951	56802	56802	56802	56802	56802	56802	56802	56802	56802	56802	56802	56802	56802	56802	56802	56802	56802
				Please Read																			
				(i) Tor steel/Mild Steel																			
				I. SAIL/TATA/RINL	M.T.	53390	53241	53241	53241	53241	53241	53241	53241	53241	53241	53241	53241	53241	53241	53241	53241	53241	53241
II. Other than SAIL/TATA/RINL	M.T.	52140	51991	51991	51991	51991	51991	51991	51991	51991	51991	51991	51991	51991	51991	51991	51991	51991	51991				
2	33	Item No. 39 of Chapter-C	R.C. weather board (1:1.5:3) with stone complete in ground floor.																				
				In Place of																			
				50 mm thick	Sq.m.	1114	1083	1068	1043	1085	1087	1094	1069	1086	1087	1059	1162	1104	1124	1098			
				Please Read																			
				50 mm thick - using steel of																			
				I. SAIL/TATA/RINL	Sq.m.	1101	1069	1055	1030	1072	1074	1081	1056	1072	1073	1053	1150	1092	1112	1086			
II. Other than SAIL/TATA/RINL	Sq.m.	1096	1065	1050	1025	1067	1069	1076	1051	1068	1069	1048	1144	1087	1107	1081							

**5TH CORRIGENDA & ADDENDA
FOR SCHEDULE OF RATES OF PWD (W.B) wef 01.12.2015
Volume-I: (For Building Works, Materials & Labour)**

(c) CORRIGENDA

Date: 04.11.2016

Sl No.	Ref. Page No.	Chapter No. & Item No.	Description of Item	Unit	Rate (Rs.)														REMARKS		
					Kolkata / 24 Pgs (N & S) /Area of Kalyani Sub Div	Bardhaman	Purulia	Birbhum	Howrah/ Hoogly	Medinipur (E)	Medinipur (W)	Bankura	Nadia excluding area of Kalyani Sub Div	Murshidabad	Malda	Darjeeling except plains of Siliguri Sub Divn.	Jalpaiguri, Aitpurazar, plains of Siliguri Sub Divn. & Area of Haldibari PS	Coochbehar excluding the area of Haldibari PS		Uttar/ Dakshin Dinajpur Dist.	
3	34	Item No. 40 a), 40 b) of Chapter-C	R.C. shelves (1:1.5:3) either precast or cast in situ with stone chips as necessary complete. In ground floor																		
			In Place of																		
			(a) 50 mm. Thick panels	Sq.m.	1163	1132	1117	1092	1135	1136	1143	1118	1135	1136	1109	1212	1154	1174	1148		
			Please Read																		
			(a) 50 mm. Thick panels -using steel of																		
			I. SAIL/TATA/RINL	Sq.m.	1150	1118	1104	1079	1121	1123	1130	1105	1122	1122	1103	1200	1142	1162	1136		
			II. Other than SAIL/TATA/RINL	Sq.m.	1145	1114	1099	1074	1116	1118	1125	1100	1117	1118	1098	1194	1137	1157	1131		
			In Place of																		
			(b) 37.5 mm. Thick panels	Sq.m.	1019	991	979	960	995	995	1000	980	995	996	975	1059	1009	1024	1006		
			Please Read																		
(b)37.5 mm.Thick panels -using steel of																					
I. SAIL/TATA/RINL	Sq.m.	1009	981	969	950	985	985	990	970	985	986	971	1049	1000	1015	997					
II. Other than SAIL/TATA/RINL	Sq.m.	1005	977	965	946	982	981	986	966	981	982	967	1045	996	1011	993					
4	35	Item No:43 of Chapter-C	Supplying,hoisting,fitting and fixing R.C.C. precast thin lintels.....same when directed.																		
			In Place of																		
				Cu.M.	13079	12646	12564	12080	12670	12540	12981	12576	12720	12855	12208	14276	13144	13433	13536		
			Please Read																		
			I. SAIL/TATA/RINL	Cu.M.	12782	12349	12267	11783	12374	12244	12685	12279	12423	12559	12088	14008	12875	13165	13267		
II. Other than SAIL/TATA/RINL	Cu.M.	12678	12245	12163	11679	12270	12139	12580	12175	12319	12455	11974	13893	12761	13050	13153					

**5TH CORRIGENDA & ADDENDA
FOR SCHEDULE OF RATES OF PWD (W.B) wef 01.12.2015
Volume-I: (For Building Works, Materials & Labour)**


(b) CORRIGENDA


ANNEXURE-I


Date: 04.11.2016

Table 1-1- ISSUE RATE OF CEMENT & STEEL MATERIALS (Page - 308 of SOR wef 01.12.2015)

Item No.	Steel Producer	Description of Items	Unit	In place of 4th Corrigendum & addendum				Please read				Remarks
				Issue Rate (Rs) (Supplied by the Department)		Basic Price (Rs) (Supplied by Contractor)		Issue Rate (Rs) (Supplied by the Department)		Basic Price (Rs) (Supplied by Contractor)		
				South Bengal	North Bengal	South Bengal	North Bengal	South Bengal	North Bengal	South Bengal	North Bengal	
1	2	3	4		5		4		5		6	
2)	SAIL/TATA/RINL	Steel Materials i)Mild Steel Rods (Fe 250)	MT	44900	46300	39750	41180	36900	38600	32500	34000	* The "Steel Producers", has been incorporated as per order no: 1825 E-in-C/2015, Dtd: 05/10/2015
		ii) Tor Steel Rods/HYSD/Fe 415/Fe 500/Fe 500D	MT	44900	46300	39750	41180	36900	38600	32500	34000	1) Rates furnished in column-4 of item 1 & 2 are the issue rates of materials at Departmental Stackyard/Godown.
	Other than SAIL/TATA/RINL	Steel Materials i)Mild Steel Rods (Fe 250)	MT	NA	NA	NA	NA	35900	37500	31571	33071	2) For sub Items of Item 2, The Basic Prices exclusive of Contractors Profit but inclusive of all Taxes & duties,are given in Column-5. To arrive at complete rate in case of Steel supplied by Contractor.Format B of Annexure - I is referred.
		ii) Tor Steel Rods/HYSD/Fe 415/Fe 500/Fe 500D	MT	NA	NA	NA	NA	35900	37500	31571	33071	


(DEBASISH ROY)
Superintending Engineer
Planning and Monitoring Circle, P.W.
Dte. & Convener of the Combined
Schedule Committee of PWD


(TAPASH KR. DEY)
Superintending Engineer
Bridge Planning Circle, P.W.(R) Dte. &
Member of the Combined Schedule
Committee of PWD


(DEBASISH ROY)
Superintending Engineer
Survey & Design Circle, P.W. Dte. &
Member of the Combined Schedule
Committee of PWD


(SRIMUMAR BHATTACHARYA)
E-in-C & E. O. Secretary
Public Works Directorate &
Chairman of the Combined Schedule
Committee of PWD